

WHERE PVC FENCING IS ADJACENT CONCRETE, TURF OR PROJECT BOUNDARY, PROVIDE A CONCRETE MOWCURB ALONG FENCE LINE. REFER TO DETAIL LC-06 & 07 FOR FOOTING ELEVATION TOP OF FOOTING MUST BE AT ELEVATION TO ACCOMMODATE 6" DEEP FORM BOARDS AND CONCRETE MOWCURB TO BE POURED AFTER FOOTING AND POST INSTALLATION REFER TO DETAIL LC-09 FOR 2 RAIL DIAMOND STYLE PVC FENCING ALL FOOTINGS ARE SUBJECT TO SAME REQUIREMENTS INDICATED ON NOTE 4 OF DETAIL LC-06

LD Consulting 2012 (Any deviation or reproduction of this design must be approved in writing by Valley-Wide Recreation & Park District)



## VALLEY-WIDE RECREATION & PARK DISTRICT

THREE RAIL PVC FENCING

LC-08

REV. 2012