



NOTES:

1. PROVIDE 4 EA. CONCRETE BRICKS UNDER VALVE BOX (TYP.)
2. CONTRACTOR SHALL PROVIDE FERTIGATION CERTIFICATION FROM MANUFACTURER
3. FERTIGATION PUMP & PANEL SHALL BE INSTALLED IN BOOSTER PUMP ENCLOSURE WHEN USED
4. PROVIDE WIRING FROM FERTIGATION CONTROL IRRIGATION CONTROLLER IN 3/4" CONDUIT
5. REFER TO MANUFACTURER'S DETAILS AND SPECIFICATIONS FOR WIRING DIAGRAM
6. PROVIDE SEPARATE 15 AMP BREAKER AND INSTALL POWER TO PUMP PER LOCAL CODE

LD Consulting 2012 (Any deviation or reproduction of this design must be approved in writing by Valley-Wide Recreation & Park District)



VALLEY-WIDE RECREATION & PARK DISTRICT

FERTIGATION PUMP AND WIRING

IR-17

REV. 2012