



NOTES:

- ALL JOINTS SHALL BE PERPENDICULAR TO CONCRETE EDGE
- ALL JOINTS SHALL BE HAND TOOLED AND SAWCUT TO A DEPTH OF 1-1/2"
- SAW CUTTING IN LIEU OF TOOLED JOINT MUST BE APPROVED IN WRITING BY THE DISTRICT
- PROVIDE 3/8" FELT EXPANSION JOINTS WHEN CONCRETE JOINS WITH WALL OR BUILDING
- PROVIDE 3/8" FELT EXPANSION JOINTS AT 30 FOOT SPACING TYP.
- PROVIDE ALL RAMP JOINT TOOLING PER ADA STANDARDS
- SPEED DOWELS SHALL BE USED BETWEEN EACH COLD JOINT POURS
- ALL REBAR MUST BE 2" FROM ANY EDGE OF CONCRETE AND BE SECURED TO A 2"X2" MINIMUM CONCRETE BLOCK AT 4' O.C. MINIMUM SPACING PER SPECS.
- DRILL AND SECURE REBAR WITH EPOXY AGAINST ALL EXISTING COLD JOINTS WITH SPEED DOWELS

LD Consulting 2012 (Any deviation or reproduction of this design must be approved in writing by Valley-Wide Recreation & Park District)



VALLEY-WIDE RECREATION & PARK DISTRICT

CONCRETE REBAR AND JOINTS

LC-03

REV. 2012