



NOTES:

1. ALL WIRING MUST CONFORM TO LOCAL CODES AND SHALL BE 24" DEEP
2. PROVIDE 24" EXPANSION COILS AT EACH WIRE CONNECTION
3. PROVIDE 3" CLEARANCE BETWEEN WIRES & BOX
4. EPOXY ALL GAPS BETWEEN WIRE AND CONDUIT AT EXPOSED SWEEP ENDS
5. PROVIDE 4 EA. CONCRETE BRICKS UNDER VALVE BOX (TYP.)
6. ACCURATE AS-BUILTS WITH TWO REFERENCE POINTS SHALL BE APPROVED PRIOR TO BACKFILLING
7. CONTRACTOR SHALL COVER BOX AFTER WIRING IS APPROVED TO PREVENT WIRE THEFT
8. ALL CONDUITS SHALL HAVE METALLIC WARNING TAPE INSTALLED 6" ABOVE CONDUIT

LD Consulting 2012 (Any deviation or reproduction of this design must be approved in writing by Valley-Wide Recreation & Park District)



VALLEY-WIDE RECREATION & PARK DISTRICT

ELECTRICAL PULL BOX

LC-35

REV. 2012