



- PLAN VIEW —
- PALM TREE PER PLAN
- 2" THICK BARK MULCH INSIDE BASIN
TAPER TO 1/2" AT CROWN
- EARTH WATERING BASIN TO REMAIN
- FINISH GRADE (SET TOP OF
ROOTBALL 4" ABOVE GRADE)
- PALM FERTILIZER SPIKES 1 EA.
PER 4" OF TRUNK DIA.
- WASHED PLASTER SAND
- 4" PERF. DRAIN PIPE W/FILTER
SOCK (SEE PLAN VIEW ABOVE)
- UNDISTURBED NATIVE SOIL TYP.
- 27" DEEP 3/4" CRUSHED GRAVEL
- 4" DRAIN PIPE W/FILTER SOCK (SEE PLAN VIEW ABOVE)

NOTES:

1. ALL BACKFILL TO BE WATER JETTED DURING PLANTING
2. ALL FRONDS TO BE TIED TOGETHER PRIOR TO PLANTING
3. FRONDS TO BE PRUNED AS DIRECTED BY THE DISTRICT
4. ALL BREATHER AND BUBBLER TUBES SHALL HAVE FILTER SOCK

LD Consulting 2012 (Any deviation or reproduction of this design must be approved in writing by Valley-Wide Recreation & Park District)



VALLEY-WIDE RECREATION & PARK DISTRICT

PALM TREE PLANTING

PL-01
REV. 2012