



NOTES:

- CONCRETE SHALL HAVE A HIGH POINT AT GOAL POST AND SLOPE TO PERIMETERS PER PLAN TO PROVIDE PROPER DRAINAGE (1% - 1.5% SLOPE REQUIRED)
- ENTIRE PLAYING AREA SHALL HAVE AN APPROVED COLORED SPORTS SURFACE
- COLORS AND LAYOUT MUST BE APPROVED PRIOR TO CONSTRUCTION
- CONCRETE SUBGRADE SHALL HAVE 8" DEEP CLASS 2 BASE COMPACTED TO 90%
- CONCRETE SHALL HAVE #4 REBAR AT 36" O.C. WITH SUPPORT BLOCKS AT 4' MIN. SPACING
- CONCRETE SHALL COMPLY WITH SOILS ENGINEERING RECOMMENDATIONS WHEN ADDITIONAL MATERIALS OR DEPTHS ARE INDICATED THAT ARE GREATER THAN DISTRICT DETAIL
- PROVIDE 1-1/2" DEEP CONCRETE SAW CUTS AT 10' SPACING

LD Consulting 2012 (Any deviation or reproduction of this design must be approved in writing by Valley-Wide Recreation & Park District)



VALLEY-WIDE RECREATION & PARK DISTRICT

BASKETBALL HALF COURT

LC-20
REV. 2012